


# Notes

1. **General**
  - 1.1. Tank constructed from Polyethylene.
  - 1.2. The MGT is to be installed in a location that will not cause a nuisance, obstruct fire access, cannot be vandalised or be damaged by vehicles.
  - 1.3. The MGT must have ease of access to pumpout point for maintenance.
  - 1.4. A hose tap fitted with RPZD backflow protection (as per AS/NZS 3500) must be installed within 5 metres of the grease trap for maintenance and cleaning.
2. **Installation above ground**
  - 2.1. The MGT is to be supported on a 100mm thick concrete pad.
  - 2.2. The MGT does not require a stand.
  - 2.3. Any maintenance platform must be installed in accordance with Australian Standard 1657-1992 allowing safe access while inspecting and maintaining the MGT
  - 2.4. All pipes connecting to the MGT shall be fully supported; there shall be no stress on the tank connections.
  - 2.5. All stormwater must be diverted away from the MGT to prevent undermining of foundation.
3. **Installation below ground**
  - 3.1. All connections to the MGT shall be in accordance with the appropriate authorities.
  - 3.2. Any excavation exceeding 1.5 metres in depth shall comply with the construction safety acts and regulations before backfilling.
  - 3.3. The MGT must be filled with water prior to backfilling.
4. **Excavation dimensions**
  - 4.1. The excavated hole width shall be kept as narrow as practicable. The depth shall not be greater than 150mm more than the required depth.
  - 4.2. 75mm clearance is required at the sides of tank.
5. **Over excavation**
  - 5.1. Where an excavation has been made deeper than required, the excess depth shall be filled either with bedding material compacted to achieve 98% compaction or concrete.
6. **Water Charged Ground**
  - 6.1. Where installation is in high water table or water charged ground, mine subsidence, filled or unstable areas, the services of a qualified structural engineer is required for certification.
7. **Bedding material**
  - 7.1. The bedding material shall be 1 part Portland cement to 4 parts clean sand.
  - 7.2. The bedding shall be thoroughly compacted by tampering at 300 mm layers.
  - 7.3. The bedding material shall encase the whole tank.
8. **Final Backfill**
  - 8.1. The final backfill material shall comply with the following:
    - 8.1.a. Spoil from the excavation of the trench may be used.
    - 8.1.b. Foreign material such as builder's waste, bricks, and concrete shall not be used.
    - 8.1.c. The backfill shall be compacted to restore the excavated hole as near as practicable to the normal ground.

# HALGAN MGT 2000 GREASE TRAP DETAIL



HALGAN MGT DIMENSIONS					
MODEL	HEIGHT	WIDTH	LENGTH	VOLUME	WEIGHT
MGT 550	1550mm	720mm	1120mm	550 L	60KG
MGT 1000	1550mm	720mm	2060mm	1000 L	100 KG
MGT 1500	1550mm	720mm	3000mm	1500 L	140 KG

					<small>THIS DRAWING AND THE INFORMATION CONTAINED HEREON ARE THE PROPERTY OF HALGAN PTY LTD AND MUST NOT BE COPIED, REPRODUCED OR USED WITHOUT THE WRITTEN PERMISSION OF HALGAN PTY LTD.</small>					
					<small>DO NOT SCALE IF IN DOUBT ASK</small>			<small>3rd ANGLE</small>		
REV	DATE	DESCRIPTION	BY	CHKD	APP	REF. DWG.	TITLE	HALGAN MGT 2000 GREASE TRAP DETAIL		
							X X X X X			
							DRAWN DN		DATE 18.10.2012	
							CHECKED SM		SCALE 1:30	
							DWG. NO. MGT2000		REV. A	